

WELL RECORD

28-5-20W

Company Cities Service Oil Co. Well No. 3 Farm Vehige
 Location 970' S. & 330' E. of W/4 Corner Sec. 28 T. 5 R. 20W
 Elevation 2186 County Phillips State Kansas
 Drig. Comm. May 19, 1942 Contractor Huber Oil & Gas Company
 Drig. Comp. June 1, 1942 Acid None
 T. D. 3664 1/2' Initial Prod. Kohometer Potential: 1819 oil, 0.2% water, 24 hrs.

CASING RECORD:

8-5/8" @ 165' cas. 125 sz cement
 5-1/2" @ 3664' cas. 150 sz Lehigh &
 Lone Star

FORMATION RECORD:

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 11 1989
 CONSERVATION DIVISION
 Wichita, Kansas

sand	0-40
sand & shells	100
shale & shells	1885
shale & lime	2732
lime & shale	3350
lime	3455
shale & lime	3530
shale & sand	3580
shale & lime	3619
cored sand (no rec.)	3624
sand	3629
cored sand (no rec.)	3634
sand	3644
sand & lime	3649
cored Granite Gneiss (rec. 1')	3654
granite wash	3664
granite	3664 1/2'

T. D.

Top Sandy Limestone	3602'
Top Reagan	3613'
Top Granite	3663'
Penetration	1 1/2'
Total Depth	3664 1/2'

June 1, 1942 - Ran Schlumberger.

June 18, 1942 - Perforated 12 shots
 3602-3606.

700' oil in 10 mins.
 2600' oil in 2 hours.
 2800' oil in 4 hours.

Syfo:	500'	0°
	1000'	0°
	1500'	0°
	2000'	0°
	2500'	0°
	3000'	0°