



28-5-20W
JW

MEMORANDUM
OCCIDENTAL OIL AND GAS

Wichita, Kansas
May 8, 1989

TO: Mr. M. D. Harrison

FROM: Mr. P. W. Pringle

SUBJECT: PLUGGING PROCEDURE..... VEHIGE "A" #3
1650' FSL - 330' FWL
SEC. 28-5S-20W
PHILLIPS CO., KS

WELL SPECS:

MAY 12 1989

8 5/8" CASING @ 165' W/125 SX
5 1/2" CASING @ 3664' W/150 SX
4" LINER 3415-3633' W/40 SX
PERFORATIONS: 3596-98'
PBSD 3633'
FILL INSIDE CASING @ 3430'
CASING LEAK @ 2463'

KANSAS GEOLOGICAL SURVEY
WICHITA BRANCH

SHALLOW FORMATION DATA:

DAKOTA 705-1000'
CHEYENNE 1095-1175'
ANHYDRITE 1715-1740'

MAY 11 1989
OCCIDENTAL OIL AND GAS
WICHITA, KANSAS

1. Prior to plugging, obtain approval of project from the KCC Field Office #4, Hays, KS (913) 628-1200.
2. Perforate at 1700' and 1050' using 4 SPF/interval.
3. Tie onto the 5 1/2" casing and pump in the hole approximately 306 sx 65/35 Pozmix + 8% gel and hulls to surface. Pressure up on casing. (Have 500# hulls at location)
4. If circulation was not established. Tie onto the 8 5/8" casing and pump 100 sx (same) cement down the annulus.
5. Let slurry set 48 hrs., check TOC and cap the well.