

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas


28-5-26

CITIES SERVICE OIL CO.  
Vehicle No. 5.

SEC. 28 T. 5 R. 20 E.  
SW NE SW  
990'S 990'W Center

Total Depth. 3665' SIM  
Comm. 7-23-43 Comp. 8-2-43  
Shot or Treated. None  
Contractor. R.W.Rine Drlg.Co.  
Issued. 10-2-43

County. Phillips



CASING:  
8 5/8" 160' Cem.  
5 1/2" 3665' Cem.

Elevation.

Production. Echo.Pot.839 B.  
No wtr

Figures Indicate Bottom of Formations.

sand	0-100
clay & shale	160
shale	730
shale & sand	1565
shy shale	1731
anhydrite	1762
shale	1800
shale & lime	2080
shale	2390
shale & shells	2810
lime & shale	2945
lime & shale brks	3035
lime & shale	3140
shale	3150
lime	3205
shale	3225
lime	3540
shale	3545
lime	3665

3665 Rot.TD equals 3665 SIM  
Ran Schlumberger

Total Depth.

Top Reagan 3606  
Granite Wash 3664

Drd cement to 3632

Perf. 12 shots 3600-11  
Perf. 22 shots 3606-10, sh oil  
Perf. 23 shots 3610-14,  
350' oil in 1/4 hr  
450' oil in 1/2 hr  
900' oil in 1 hr  
1700' oil in 2 hrs  
2600' oil in 6 hrs