

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas


23-5-206

Company - CITIES SERVICE OIL COMPANY
Farm - Vohige "A" No. 7

SEC. 28 T. 5 R. 20W
NE NW SW
330' S, 990' E of W/4 corner

Total Depth. 3631'
Comm. 12-24-48 Comp. 1-14-49
Shot or Treated. none
Contractor. R. W. Rino
Issued. 3-12-49

County. Phillips
KANSAS



CASING:

8 5/8" 206' cem w/250 sx.
5 1/2" 3625' cem w/150 sx.

Elevation. 2202 Ind.

Production. Phys. Pot. 253 oil,
no water, 24 hrs.

Figures Indicate Bottom of Formations.

clay, shale, sand	206
shale, sand, shells	1715
anhydrite	1750
shale, shells	2755
lime, shale	3315
lime	3475
lime, shale	3605
lime	3610
cored, sandy shale, lime and shale	3615
cored, shale, shale Sdy	3621
cored, shale, sand	3627
3627 RTD = 3625 SLM	
sand	3631
Total depth	

Tops Corrected:

Lansing	3359
Reagan	3624
Penetration	7'

FILLUP:

700' oil in 1/2 hr.
1100' oil in 1 hr.
1810' oil in 1 hr. 40 mins.
1-17-49, pumped 318 oil, trace
water 24 hrs.