

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 412 Union National Bk Bldg., Wichita, Kansas


78-5-206

CITIES SERVICE OIL CO.
 Vehige "B" No. 1.

SEC. 28 T. 5 R. 20 W
 SW¹/₄ NW
 330' N 330' E W¹/₄ Cor.

Total Depth. 3675' SIM
 Comm. 9-6-43 Comp. 9-17-43
 Shot or Treated. None
 Contractor. R.W. Rine Drlg. Co.
 Issued. 11-13-43

County. Phillips



CASING:
 8 5/8" 159' Cem.
 5 1/2" 3675' Cem.

Elevation.

Production. Echo. Pot. 1903 B.
 6% wtr

Figures Indicate Bottom of Formations.

sand, shale & shells	0-159
shale & sand	1010
shale, sand & shells	1560
shale	1730
anhydrite	1945
shale & lime	2060
shale & shells	2145
shale	2295
shale & lime	2440
shale & shells	3338
lime	3675
3675 Rot. TD = 3675 SIM	
Total Depth.	

Ran Schlumberger

Tops: Reagan	3618
Schist	3652
Penetration	25

Drld cement 3641
 Perf. 12 shots 3630-34
 325' oil in 20 min
 585' oil in 30 min
 Perf. 12 shots 3630-34
 1585' oil in 1 hr
 2700' oil in 6 1/2 hrs