

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

28-5-204

Company- CITIES SERVICE OIL CO.  
Farm- Vehige "B" No. 3

SEC. 28 T. 5 R. 20W  
NE SE NW  
990' N  
330' W of center sec.  
County Phillips  
KANSAS

Total Depth. 3612'  
Comm. 10-12-53 Comp. 10-28-53  
Shot or Treated. 500 gals. 11-24-53  
Contractor. R. W. Rine Drilling Co.  
Issued. 1-9-54



CASING:  
8 5/8" 207' cem. w/250 sx  
5 1/2" 3603' cem. w/150 sx

Elevation. 2198' Gr.

Production. Phy. Pot. 99 BO & NW  
24 hrs.

Figures indicate Bottom of Formations.

sand, shale, shells	207
shale & shells	325
shale, shells & sand	1225
anhydrite	1235
shale & shells	2285
lime & shale	2990
lime	3085
lime & shale	3372
lime	3385
lime & shale	3440
lime	3490
lime & shale	3605
lime	3609
lime 3609 RTD=3607 SLM	3612
Total Depth	

TOPS: (Corrected)

Topeka	3106
Heebner	3315
Dodge	3341
Lansing	3356
Gorham	3599
Arbuckle	3602

Penetration 10'

Fillup: 170' oil in 1 hr. @ 3610  
260' oil in 1 1/2 hrs.  
295' " " 2 hrs.  
392' " " 3 hrs. 25 min. @ 3612'  
447' " " 3 hrs. 55 min.  
774' " " 8 hrs.  
1404' " " 20 hrs.