

Flooded
L.M.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


29-5-20w

CITIES SERVICE OIL CO.
Noel No. 1.
'A'

SEC. 29 T. 5 R. 20W.
SW SE SE
318' N & 990'W of SE corner.

Total Depth. 3602
Comm. 1-14-41 Comp. 2-1-41
Shot or Treated. None
Contractor. Hissom & Wolfe Drilling Co.
Issued. 3-15-41

County Phillips



CASING.

103/4" 155' cemented.
5 1/2" 3585' cemented.

Elevation.

Production. Pot. 3065 B.

Figures Indicate Bottom of Formations. Echo-Meter no water.

shale and shells	155
shale	1109
shale and lime	1500
shale and red bed	1720
anhydrite	1755
shale and lime	1905
shale and shells	2040
lime and shale	2335
broken lime	2390
lime and shale	2798
broken lime	2909
lime	2984
lime and shale	3059
lime	3176
broken lime	3250
lime	3587 3587
3587 Rotary T.D. = 3588 S.L.M.	
dolomite & sand 3588-	3593
sand	3602

Total Depth.

Corr. Top Arbuckle 3583
Top Reagan sand 3591
Penetration 11'

FILLUP.

200' oil in 50 Min.
400' Oil in 1 hr 20 Min.
800' oil in 2 hrs 20 Min.
1200' oil in 4 1/2 hrs.
1500' oil in 7 hrs.
2800' oil in 10 1/2 hrs.
2900' oil in 13 1/2 hrs.