

Plotted gas


29-5-20W

CITIES SERVICE OIL CO.
Well No. 2.
(A)

SEC. 29 T. 5 R. 20 W
SWc SE
330' N 330' E S $\frac{1}{4}$ Cor.

Total Depth. 3584'
Comm. 10-18-41 Comp. 10-30-41
Shot or Treated. None
Contractor. R.W. Rine Drlg. Co.
Issued. 12-6-41

County. Phillips



CASING:
8 5/8" 166' Cem.
5 1/2" 3577' Cem.

Elevation.

Production. Echo. Pot. 2373 B.
No wtr

Figures Indicate Bottom of Formations.

surface & shale	0-166
shale, shells, sand	1120
shale & sand	1595
shale	1695
lime brkn	1732
shale & shells	1850
shale	2250
shale & lime	2405
shale & shells	2570
lime & shale	2815
shale & lime	2895
shale & lime shells	3040
shale & shells	3145
lime & shale	3245
lime	3447
lime brkn	3537
lime	3574
cored lime & sand (rec. 2 1/2')	3577
3577 Rot. TD=3577 SLM	
sand	3584
Total Depth.	

Tops: Arbuckle 3561
Reagan 3576
Penetration 8

Fillup:

1700' oil in 35 min.
2450' oil in 1 hr, 20 min.
2600' oil in 1 hr, 35 min.
2850' oil in 3 1/4 hrs