

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bank Bldg, Wichita, Kansas.

Plotted gas
29-5-20W

CITIES SERVICE OIL CO.
Pinkerton No. 4

SEC. 29 T. 5 R. 20 W
NE SE SW
990' N 330' W of S $\frac{1}{4}$ cor.


Total Depth. 3610
Comm. 11-17-41 Comp. 11-30-41
Shot or Treated. None.
Contractor. R.W. Rine Drilling Co.
Issued. 1-10-42

County Phillips.

CASING.

85/8" 160' Cemented.
5 1/2" 3600' cemented.

Elevation.



Production Pot. 2117 B.
no wtr 24 hours.
Echometer.

Figures Indicate Bottom of Formations.

sand and shale	100
shale and shells	160
shale shells & sand	1205
shale and sand	1568
shale and shells	1720
anhydrite	1755
shale and shells	1945
shale and lime shells	2115
shale and shells	2334
shale and lime	2464
shale	2610
shale stinky	2676
shale and lime	2920
shale	3040
shale and shells	3145
shale and lime	3346
lime	3394
chert and lime	3431
lime	3582
shale and lime	3609
cored sand (rec 4 1/2)	3614
3614 Rot. T.D. - 3609 SLM.	
sand	3610

Total Depth.

Corr. Top Arbuckle 3595
Corr. Top Reagan 3603
Penetration 7'
Total Depth 3610

Fillup : 2625' oil in 45 Min.
2775' oil in 1 hour.