


Plotted F.S.
29-5-20W

CITIES SERVICE OIL CO.
Pinkerton No. 5

SEC 29 T. 5 R. 20 W
SW NE SW
990' S 990' W of center.

Total Depth, 3691
Comm. 12-23-41 Comp. 1-4-42
Shot or Treated. None.
Contractor. R.W. Rine Drilling Co.
Issued. 2-28-42

County Phillips



CASING

85/8" 171' cemented,
5 1/2" 3691' cemented.

Elevation 2233 *act*

Production Pot. 3005 B

Figures Indicate Bottom of Formations, no wtr. Depth.

sand and shale	100
shale and shells	600
shale shells & sand	1540
shale	1735
lime and shale	1795
shale and shells	2865
lime broken	2955
shale and shells	3100
shale and lime	3228
lime broken	3380
lime	3671
sand	3678
shale	3691

Total Depth.

Top Arbuckle	3628
Reagan	3659
Base Reagan	3674

January 13, 1942 Perf. Arbuckle as follows.

12 shots	3630-34	175' oil in 15 Min.
		450' oil in 25 Min.
12 shots	3634-38	1100' oil in 45 Min.
		1700' oil in 1 hr.
		2100' oil in 1 1/4 hours.
12 shots	3636-40	2440' oil in 1 hr 40 min.
11 shots	3630-35 1/2	2670' oil in 2 hours.