

*Plotted.*

*29-5-20W*

CITIES SERVICE OIL CO.  
Reese "D" No. 1.

SEC. 29 T. 6 R. 20 W  
SWE NE  
330' N 330' E of Center

Total Depth. 3723-3727 SIM  
Comm. 5-25-42 Comp. 6-3-42  
Shot or Treated. None  
Contractor. R.W. Rims Drlg. Co.  
Issued. 7-25-42

County. Phillips



CASING:  
8 5/8" 162' Com.  
5 1/2" 3727' Com.

Elevation. *2225 act*

Production. Depth. Pot. 1314B.  
No wtr

Figures Indicate Bottom of Formations.

shale & sand	162
sand, shale, shells	1755
anhydrite	1796
shale & shells	2125
shale red & shells	2347
lime & shale	3323
lime	3499
lime & shale	3618
lime	3640
scored lime & sand (rec. 4')	3644
lime	3649
lime & shale	3720
granite	3723

3723 Rot. TD = 3727 SIM  
Total Depth.

Corr. Top Arbuckle	3633
Corr. Top Reagan	3650
Corr. Top Granite	3722
Penetration	5

Drilled cement to 3693.  
6-9-42 Perf. 12 shots 3668-71  
2410' wtr in 2 hrs  
Set Lane-Wells plug 3658-62  
Bailed dry & perf. 18 shots  
3648-52, 6-10-42

Fillup:  
800' oil in 1/2 hr  
1000' oil in 40 min.  
1400' oil in 1 hr  
2500' oil in 2 hrs  
2800' oil in 6 hrs

Put 6' cement plug 3658-3652  
on top of Lane-Wells Bridge  
plug.