

29-5-20W


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Reasa "D" No. 3

SEC. 29 T. 5 R. 20W
S. 1/4 NE
990' S and 330' E of N/4 Cor.

County. Phillips
KANSAS

Total Depth. 3632'
Comm. 8-23-47 Comp. 9-1-47
Shot or Treated. None
Contractor. R. W. Ring Drilg. Co.
Issued. 10-18-47



CASING:
8-5/8" 199' W/250 Sx. Cam.
5-1/2" 3631' W/150 Sx. Cam.

Elevation. 2193 ~~47~~ + rh

Production. Phy. Pot: 308 Oil,
21% wtr, 24 hrs.
(9-11-47)

Figures Indicate Bottom of Formations.

surface clay & sand	200
shale	250
shale & sand	1035
sand & shale	1750
shale	2095
shale w shells	2505
shale & lime	2695
shale & shells	2815
shale & lime	3210
lime, shale & chert	3280
shale & lime	3360
lime	3430
lime & chert	3480
lime	3612
shale & lime	3620
cored shale w sand (Rec. 4')	3624
cored shaley sand (Rec. 3')	3627
cored sand (Rec. 4')	3632

3632 Rotary T. D. = 3632 S. L. M.

TOPS:
Lansing 3373'
Reagan 3623'
Penetration 9'
Total Depth 3632'

Fill-up
125' fluid in 15 minutes.
1000' fluid in 45 minutes.
1500' fluid in $1\frac{1}{2}$ hours.
1975' fluid in $3\frac{1}{2}$ hours.
2225' fluid in $6\frac{1}{2}$ hours.

7-7/8" Rotary Hole.