

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas

29-5-20W

Company - CITIES SERVICE OIL CO.
Farm - Walgren "A" No. 4

SEC. 29 T. 5 R. 20W
NE NE SE
330' S & 330' W of E $\frac{1}{4}$ Corner

County. Phillips

KANSAS

Total Depth. 3629' S.L.M.

Comm. 8-29-48


Comp. 9-6-48

Shot or Treated. Acid. W/100 gals. 3614-21 $\frac{1}{2}$ ' (9-12-48) , 2000 gals. 3614-21 $\frac{1}{2}$ '

Contractor. R. W. Rine Drlg. Co.

Issued. 12-4-48

(9-16-48).



CASING:
8-5/8" 202' Cem. W/250 Sx.
5-1/2" 3627' Cem. W/150 Sx.

Elevation. 2208 Ind.
2206 set

Production. Echo. Pot. 1318 oil,
no wtr, 24 hours.

Figures Indicate Bottom of Formations.

sand	95
shale & shells	200
sand & shale	825
shale & shells	1190
lime & shale	1375
shale & shells	1710
anhydrite	1740
shale	1745
shale & shells	2600
lime & shale	2975
lime & shale	3625
lime	3619
lime & sand	3631
3631 Rot. TD - 3629 SLM	
Total Depth	

Tops, Corr.:

Lensing	3368
Arbuckle	3613
Reagan	3626
Penetration	3

Drilled out cement to
3622 SLM. Perf. 26 shots
3614-21 $\frac{1}{2}$ '. Acidized
1000 gals. 3614-21 $\frac{1}{2}$ '.
Pumped 383 oil, no wtr,
24 hrs. Acidized 2000
gals. 3614-21 $\frac{1}{2}$ '.
Pumped 447 oil, no wtr,
24 hrs.

Drilled cement & cleaned
out to bottom rotary hole, 3629.