

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


29-5-20w

Company - CITIES SERVICE OIL COMPANY
Farm - Wallgren "B" No. 3

SEC. 29 T. 5 R. 20W
SW NE NW
990' S & 990' W of $N\frac{1}{4}$ corner

Total Depth. 3614'
Comm. 4-14-47 Comp. 4-28-47
Shot or Treated. Acid. w/500 gallons. (5-1-47)
Contractor. R. W. Rine Drilling Co.
Issued. 7-5-47

County. Phillips
KANSAS



Elevation. 2193 act 4th

CASING:

8-5 /8" 198' Cem. w/250 sx
5-1 /2" 3607' Cem. w/150 sx

Production. Phy. Pot. 205 BO,
no wtr, 24 hrs.

Figures Indicate Bottom of Formations.

surface hole 0-200
shale & sholls 590
shale, sholls & sand 1730
shale & sholls 2253
shale & lime 2425
shale & sholls 2592
shale & lime 2850
shale & sholls 2950
shale & lime 3130
lime 3455
lime & shale 3499
lime 3612
3612 RTD = 3609 SIM
lime 3614
Total Depth

Ran Schlumberger

Tops :
Lansing 3374
Arbuckle corr. 3606
Penetration 8

Fillup:

475' oil in $\frac{1}{2}$ hr.
565' oil in 55 mins.
600' oil in 1 hr. 10 mins.
840' oil in 2 hrs. 20 mins.
1000' oil in 4 hrs.
1380' oil in $5\frac{3}{4}$ hrs.
2000' oil in $17\frac{3}{4}$ hrs.