

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas


29-5-20W

Company - CITIES SERVICE OIL CO.
Farm - Wallgren "B" No. 4

SEC. 29 T. 5 R. 20W
ONE NE NW
330' S & 330' W of N $\frac{1}{4}$ Corner

Total Depth. 3589' SLM
Comm. 10-11-48 Comp. 10-20-48
Shot or Treated. Acid. w/1000 gals. 10-26-48
Contractor. R. W. Mine Drlg. Co.
Issued. 12-18-48

County. Phillips
KANSAS



Elevation. 2153' Ind.

Production. Phy. Pot. 95 BO, no
wtr, 24 hrs.

CASING:

8-5/8" 171' Cem. w/200 Sx.
5-1/2" 3589' Cem. w/150 Sx.

Figures Indicate Bottom of Formations.

sand	100
shale	168
shale & sand	735
shale	1345
shale & sand	1695
anhydrite	1735
shale & shells	2255
shale & lime	3160
lime	3580
cored sdy dolomite	3583
(rec. 2 $\frac{1}{2}$ ')	
cored sdy dolomite	3586
(rec. 2'-3")	
cored sdy dolomite	3590
(rec. 3 $\frac{1}{2}$ ')	
cored sdy dolomite	3594
(rec. 4')	
3594 RTD = 3589 SLM	
Total Depth	

Tops, Corr.:

Lansing	3326
Arbuckle	3566
Penetration	23
Perf. Pen. Arbuckle	18

Drilled cen. to 3585 SLM
Perf. 67 shots 3564-3584.
 $\frac{1}{2}$ bailer muddy oil in 25 mins.