


30-5-25W

CITIES SERVICE OIL CO.
States "A" No. 3

SEC 30 T. 5 R. 20 W
SW NE SE
990' S 990' W of E $\frac{1}{4}$ cor.

Total Depth. 3652
Comm. 9-12-42 Comp. 9-27-42
Shot or Treated.
Contractor. R.W. Rine Drilling Co.
Issued 11-28-42

County Phillips.



CASINB.

103/4" 150' cemented.
7" 3644' cemented.

Elevation. 2232

Production. Pot. 74 BO.
no wtr. physical

Figures Indicate Bottom of Formations

surface	40
surface clay and sand	150
shale and shells and sand	1550
shale and red beds	1890
shale and shells	2670
shale and lime	2880
lime and shale	2954
shale	3055
shale and lime	3145
shale and shells	3230
lime	3461
lime & oher	3500
lime	3643
sand	3650

3650 Rot. T. D. = 3650 SLM
sand 3652
Total Depth.

Top Reagan 3643'
Penetration 9'

Fillup 190' oil in 3 hours.
280' oil in 6 hours.
365' oil in 9 hours.
800' oil in 21 hours.

Sept. 29, 1942 Bailed hole dry and
perforated sand with 24 shots 3644-
3650

Fillup - 125' oil in 15 Min.
325' oil in 2 hours.
375' oil in 3 hours.
1100' oil in 18 hours.

1000 gal. 7 $\frac{1}{2}$ % Acid 10-3-42