


31-5-20W

CITIES SERVICE OIL CO.
Pinkerton No. 7.

SEC. 31 T. 5 R. 20 W
SW NE NE
990'S 990'W NE Cor.

Total Depth. 3626'
Comm. 5-4-42 Comp. 5-18-42
Shot or Treated. None
Contractor. R.W. Rine Drlg. Co.
Issued. 7-11-42

County. Phillips



CASING:
8 5/8" 150' Cem.
5 1/2" 3620' Cem.

Elevation. 2214

Production. Echo. Pot. 2500 BO,
no wtr

Figures Indicate Bottom of Formations.

surface clay & sand	130
red rock	150
mud & shale	945
shale & sand	1670
shale & shells	2075
anhydrite & shale	2210
shale & shells	2448
lime & shale	2935
shale	2962
lime	3055
shale & shells	3153
lime	3448
lime cherty	3454
lime	3500
lime & shale	3563
lime brkn & shale	3605
shale & lime	3623
3623 Rot. TD=3621 SLM	
sand	3626
Total Depth.	

Corr. Top Reagan 3619
Penetration 7

Fillup:
1900' oil in 30 minutes
2600' oil in 2 hrs
2750' oil in 4 1/2 hrs