


BARNETT DRILLING CO.
 Ray "B" No. 1

SEC 32 T. 5 R. 20 W
 NEc NW

Total Depth. 3601
 Comm. 6-17-41 Comp. 9-6-41
 Shot or Treated.
 Contractor.
 Issued. 3-14-42

County Phillips.



CASING.

10" 135'
 5 1/2" 3593'4"

Elevation.

Production Pot. 3763 B.

Figures Indicate Bottom of Formations.

cellar	8
clay and shale	30
sand	65
sdv lime	70
sand rock	166
shale lime shells	310
shale shells	980
sand	1120
sdv lime	1162
shale and shells	1185
shale	1405
brown shale & lime	1530
shale	1710
anhydrite	1730
shale and shells	1750
red rock	1780
shale	2009
broken shale, sand and lime	2235
sdv lime	2401
shale	2431
sdv lime	2452
shale and lime	2580
lime	2600
shale	2645
lime and shale	2735
lime and shale breaks	2814
shale and lime	2882
shale lime shells	2950
lime	2974
shale & lime	3164
lime	3408
lime and chert	3488
lime	3536
shale	3586
Core 3586-90 Rec. 2' white sand, pyrite and shale green	
sand	3594 show oil
3594 equals 3594'4" S.L.C. drilled out cement and bailing.	
sand 3596 1/2- 3601	
Total Depth.	