



Operator

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.  
#1-W

Lease Name  
Ray "B"

SWDW

s32 T 5S R 20 W

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Driller's Log attached			Dakota Sand Cedar Hills Sd. B/Cedar Hills T.D.	1096 (+1094) 1200 (+ 980) 1440 (+ 740) 1505



USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

BARNETT OIL COMPANY

By: *Jack S. Briggs*  
Signature

Partner

Title

May 23, 1974

Date

25-2-1000

32-5-20W

State Geological Survey  
WICHITA, BRANCH

CONTRACTOR'S WELL LOG

OPERATOR:	Barnett Oil Company
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	RAY "B" #1-W (SWD)
LOCATION:	SW NE NW Sec. 32-5S-20W Phillips County, Kansas
GEOLOGIST:	
SPUD DATE:	January 29, 1974
COMPLETION DATE:	January 30, 1974



0	47	Clay
47	85	Sand
85	175	Clay and Shells
175	1096	Shale
1096	1170	Sand
1170	1505	Shale and Sand
	1505	Rotary Total Depth

Drilled 219' of 12½" surface hole. Set 5 joints of 8-5/8" casing at 209' w/150 sx. Sunset cement. Cement circulated. Job completed at 2:15 a.m. 1-29-74. Ran 41 joints of used 5½" casing set at 1204' cemented w/150 sx. common cement and 150 sx. Halliburton light cement. Job completed at 12:15 a.m. 1-30-74.

STATE OF KANSAS        )  
                                  ) SS  
COUNTY OF SEDGWICK )

Jerry A. Langrehr, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the RAY "B" #1-W, SW NE NW, Section 32-5S-20W, Phillips County, Kansas.

ABERCROMBIE DRILLING, INC.  
By: Jerry A. Langrehr  
Jerry A. Langrehr  
Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 4th day of February, 1974.

Beverly Mann  
Beverly Mann, Notary Public

My Commission Expires:  
February 10, 1975