

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


Pl R.P.K.
32-5-20W

CITIES SERVICE OIL CO.
Ray "B" No. 2

SEC. 32 T. 5 R. 20W.
NE SE NW
1050' No. 390' West of Center.

Total Depth. 3585
Comm. 8-16-41 Comp. 8-28-41
Shot or Treated. 1000 Gal (9-5-41)
Contractor. R.W.Rine Drilling Co.
Issued. 11-8-41

County Phillips



CASING.

85/8" 165' cem.
5 1/2" 3563' cem.

Elevation. 2164

Production. Pot. 1661 B.
Echometer No wtr.

Figures Indicate Bottom of Formations.

surface	30
sand	60
shale and shells	1235
sand	1400
shale and shells	1540
shale	1695
anhydrite	1730
shale and shells	2100
shale and lime shells	2420
lime and shale	3025
lime	3136
broken chert	3140
lime and shale	3190
lime	3347
chert	3348
lime and chert	3378
lime and shale	3434
lime	3563
sand	3564
3564 Rot. T.D. Equals	3564 SLM
sand	3585
Total Depth.	

Top Reagan 3563
Penetration 22'

FILLUP- 325'in 1 1/2 hours 3568
400'in 2 1/2 hours 3568
1175'in 4 1/2 hours 3573
2025'in 6 1/2 hours 3578
2525'in 9 hrs 3582
2675'in 11 hrs 3585