

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

33-5-20W

Company- CITIES SERVICE OIL CO.
Farm- Hansen "B" No.3-A

SEC. 33 T. 5 R20W
SW NE NW
940' S & 1090' W of N/4c

Total Depth. 3538

Comm. 9-17-55


Comp. 10-3-55

Shot or Treated.

Contractor. Barbour Drilling Co.

Issued. 11-19-55

County Phillips
KANSAS



CASING:

8 5/8 @ 200' w/ 225 sx cmt.
5 1/2 @ 1977' w/ 500 sx cmt.

Elevation. 2137

Production Pot. 200 BOPD, NW

Figures Indicate Bottom of Formations.

clay & sand	90
shale	200
shale & shells	810
sand	940
shale	1150
sand	1385
shale	1415
shale, sand & red bed	1635
shale	1950
anhydrite	1985
shale	2005
shale & shells	2270
lime & shale	2905
shale	3035
lime & shale	3105
lime	3170
lime & shale	3235
lime	3462
lime & shale	3510
lime	3532
cored - sand	3535
SLM	3537
sand	3538

Total Depth
3535 Rotary TD = 3537 SLM

TOPS* (corrected)

Heebner	3233
Dodge	3258
Lansing	3277
Arbuckle	3518
Reagan	3534
Penetration	4

FILLUP:

%11' oil in 1 hr.
728' oil in 1½ hrs.
900' oil in 2 hrs.
1183' oil in 3 hrs.
1410' oil in 4 hrs.
2549' oil in 18 hrs.