

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

33-5-20W


Company - CITIES SERVICE OIL CO.
Farm - Hansen "B" No. 6

SEC. 33 T. 5 R. 20W
NE NE NW
330' S & 330' W of N $\frac{1}{4}$ Corner

Total Depth. 3580'
Comm. 9-30-48 Comp. 10-16-48
Shot or Treated. Acid. W/1000 gals. 3550-66 (10-14-48).
Contractor. " " Rine Drlg. Co.
Issued. 12-4-48

County. Phillips

KANSAS



Elevation. 2180

Production. Deptho. Pot. 2178 oil,
no wtr, 24 hours.

CASING:

8-5/8" 175' Cem. W/200 Sx.
5-1/2" 3573' Cem. W/150 Sx.

Figures Indicate Bottom of Formations.

clay & sand	50
rock	60
shale	186
sand & shale	1150
shale	1690
anhydrite	1720
shale	1940
shale & shells	2520
shale	2600
lime & shale	3395
lime	3577
cored sand (no rec.)	3580
3580 Rot. TD = 3576 SLM	
sand	3580
Total Depth	

Tops, Corr.:

Lansing	3312
Arbuckle	3552
Reagan	3571
Penetration	9

Drilled cement to 3573 SLM

Perf. 60 shots 3550-66
115' oil in 1 hour
900' oil in 14 hrs.

Acidized W/1000 gals. 3550-66

10-16-48 Pumped 154 oil, 1% B.S.,
in 22 hours.

Drilled shoe & deepened 3576-80.

Hole filled from 2000' to 2700' in
2 hrs. 45 mins. at 3580'.