

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


33-5-20W

Company- CITIES SERVICE OIL CO.
 Farm- Hansen "B" No. 8

SEC. 33 T. 5 R. 20W
 NE SE NW
 990' N & 330' W of Cent.

Total Depth. RTD 3545 SLM 3546
 Comm. 10-23-52 Comp. 10-30-52
 Shot or Treated.
 Contractor. R. W. Rine Drilling Co.
 Issued. 1-17-53

County Phillips
 KANSAS



Elevation. 2148

Production. POT. 123 BO, no wtr.
 24 hrs.

CASING:

8 5/8 204' w/ 200 sx cement
 5 1/2 3543' w/ 150 sx cement

Figures indicate Bottom of Formations.

surface clay & sand	90
clay & shale	204
chalk & shale	500
shale & shells	1680
anhydrite	2570
lime & shale	3051
lime	3535
lime & shale	3540
cored: sand & sandy shale	
rec. 3'	3545
Total Depth	3545 RTD = 3546 SLM

TOPS: Corr.	
Heebner	3256
Dodge	3280
Lansing	3298
Gorham sand	3543
Penetration	3

Fillup:

200' oil in 1 hr.
 343' oil in 1 hr. 50 mins.
 503' oil in 2 hrs. 50 mins.
 643' oil in 3 hrs. 50 mins.
 843' oil in 5 hrs. 50 mins.
 1403' oil in 13 hrs. 50 mins.
 1525' oil in 15 hrs. 50 mins.