

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


34-5-20W

Company: CITIES SERVICE OIL CO.
Farm: Pearson "B" No. 4

SEC. 34 T. 5 R. 20W
CS/2 NE NW NW
530' S & 990' E of NW cor.

County Phillips

KANSAS



Total Depth. 3720
Comm. 4-15-53 Camp. 5-1-53
Shot or Treated.
Contractor. R. W. Rine Drilling Co.
Issued. 7-18-53

Elevation. 2124

Production. S. W. D. W

CASING:

10 3/4 set at 200' w/ 250 sx cement
7 in. set at 3651' w/ 150 sx cement

Figures indicate bottom of Formations.

sand, shale & shells	0-	1150
shale & shells		2440
lime & shale		3130
lime, shale & sand		3225
shale & lime		3295
lime		3641
Cored; rec 4'4" sandy shale		
shaley sand & shaley dolomite	3646	
Cored; rec 4' dolomite &		
sandy shale	3651	
Cored; rec 4'6" sandy shale,		
glauconite & sand	3656	
SLM	3652	
sand & shale	3689	
sand, shale & granite wash	3708	
granite wash & granite	3720	
Total Depth		

TOPS: (corrected)

Heebner	3347
Dodge	3370
Lansing	3385
Gorham sand	3633
Arbuckle	3640
Reagan	3649
Granite wash	3701
Granite	3719
Penetration	1