

285435

September 1944

Cities Service #1 Griffin
Section 27-58-20W, SW NW
Elev. 2180' ^{7F} (Printed)

Rotary

Pennsylvanian Conglomerate

Rare oil-stained fine sand clusters and a trace of
chert are present in circulation samples at 3561'.

Arbuckle Top 3562' Penetration 106'

Subsea -1382'

Pre Cotter 3562'- 3668'

3562-3656' Hverleigh. Sandy dolomite with glauconite. Inter-
bedded layers of oil-stained dolomitic sand through-
out.

3656-3668' Reagan. Coarse rounded frosted sand grains, loose in
rotary samples.

Pre Cambrian Top 3668' Penetration 19'

Subsea -1483' -1486

3668-3687' Poor samples with a gap from 3680-3686'. Scout top
of Wash 3668' and granite 3682'.

Remarks: Producer.

RFW:HL