

Cities Service, # C-2 Ray
SW NW NE, 32-5S-20W
Elev. 2154'
Rotary

Pennsylvanian Conglomerate 3535-3545'

3535-3540 Dense white marine limestone with coarse
round imbedded sand grains.
3540-3545 Green clay, slightly calcareous, with
imbedded medium round sand grains. Some
sandy limestone as above. (interbedded?)

Arbuckle Top 3545' Penetration 21' Subsea -1391'
3545-3551 Dolomite, coarsely crystalline, sandy to
very sandy. Glauconite rare and is
earthy rather than as pellets.
3551-3553 Friable, coarse, dolomitic sand. Reagan.
3553-3566 TD No samples.

RFW & ML