

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

15-147-00538


33-5-20W

Company. CITIES SERVICE OIL CO.
Farm. Kohman No. 3

SEC. 33 T. 5 S. 20W
NE NW NE
330' S, 990' E of N/4 cor.

Total Depth. 3548
Comm. 12-11-48 Comp. 1-9-49
Shot or Treated. 1000 gals, 1-2-49
Contractor. R. W. Rino Drlg. Co.
Issued. 3-12-49

County. Phillips
KANSAS



CASING:
8 5/8" 195' cem. w/250 sx.
5 1/2" 3531' cem w/150 sx.

Elevation. 2135 Ind.

Production. Phys. Pot: 236 oil,
no wtr, 24 hrs.

Figures Indicate Bottom of Formations.

clay, sand	90
shale	195
shale, sand	1655
anhydrite	1690
shale, sholls	2625
shale, lime	3234
lime	3440
lime, shale	3518
cored: limo, shale and sand	3521
dored: sand, shale and lime	3526
lime, sand	3531
3531 RTD = 3533 SLM	
lime	3538
sand	3548
total depth	

Tops:

Lansing	3278 Corr:
Arbuckle	3526 Corr;
Reagan	3538
Penetration	10'

2 bailers oil in 1 hr @ 3535.
140' oil in 1 hr, 10 mins at 3538.
1120' oil in 12 hrs. at 3538'.
1-2-49 az. 1000 gals. at TD 3538.
Pumped 2.65 bbls. oil pr hr.
1-7-49, deepened 3538-44.
1-8-49, pumped 72 oil, no wtr, 10 hrs.
1-9-49, deepened 3544-48.
1-10-49, pumped 153 oil, no wtr, 16 hrs.