

K. G. S. LIBRARY

KANSAS

18-5-JW

WELL COMPLETION REPORT
DRILLERS LOG

API No. 15 — County — Number —

State Geological Survey
WICHITA BRANCH

S. 18 T. 5 R. 21 W
Loc. SW, NW, NW
County Norton

Operator OZARK ENTERPRISES JUL 8 0 REC'D

Address Box 427, Logan, KS 67646

Well No. 6 Lease Name Noone


Footage Location

feet from (N) (S) line feet from (E) (W) line

Principal Contractor Abeacrombie Geologist Roger Welty

Spud Date 6-5-80 Date Completed 6-11-80 Total Depth 3536 P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser



Elev.: Gr. 2107

DF KB 2112

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
<u>SURFACE</u>	<u>12 1/4"</u>	<u>8 7/8"</u>	<u>20#</u>	<u>205'</u>	<u>Com</u>	<u>180</u>	<u>3% CA, 1, 2% 90L</u>
<u>Prod</u>		<u>4 1/2"</u>	<u>9 1/2#</u>	<u>3534'</u>	<u>Com</u>	<u>150</u>	<u>" " " "</u>

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
<u>OH²</u>	

INITIAL PRODUCTION

Date of first production 7-10-80 Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS

Oil 8 bbls. Gas 80 bbls. Water 80 bbls. Gas-oil ratio CFPB

Disposition of gas (vented, used on lease or sold) Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator CRAY. ENCOMPRES		DESIGNATE TYPE OF COMP - OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 6	Lease Name NOONE	oil	
S ☐ T ☐ R ☐ E ☐ W ☐			
WELL LOG Show all important zones of porosity and contents thereof; cor'd intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
ANHYDRITE	+405		
Base ANY	+376		
Heebneer	-1127		
TORONTO	-1151		
LANSING	-1172		
BKC	-1358		
REAGAN	-1424		
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	Signature Stephen P. Morrison Title Operator Date 7-19-80		

State Geological Survey
WICHITA BRANCH
JUL 3 0 RECD

18-5-21W
SW-NW-NW

CONTRACTOR'S WELL LOG

OPERATOR: Ozark Enterprises
CONTRACTOR: Abercrombie Drilling, Inc.
WELL NAME: NOONN #6
LOCATION: SW NW NW, Section 18-5S-21W
Norton County, Kansas
SPUD DATE: 06-05-80
COMPLETION DATE: 06-11-80

0	1255	Sand & Shale
150	1440	Sand
1440	1590	Sand & Shale
1590	1707	Shale
1707	1735	Anhydrite
1737	1920	Sand & Shale
1920	2580	Shale
2580	2790	Shale & Lime
2790	2960	Shale
2960	3260	Shale & Lime
3260	3536	Lime
	3536	Rotary Total Depth

Spud @ 4:00 p.m. Drilled 208' of 12-14" hole. Ran 5 joints of 8-5/8" 20# casing. (Tally 199.72') Set at 205' K.B. Cemented with 165 sacks of common, 2% gel, 3% Ca. Cl. Pumped to 190' K.B. Plug down @ 9:30 p.m. 06-05-80. Cement did circulate.

T.D. 3536', 11:00 06-10-80. Ran 88 jts. of 4-1/2" - 9-1/2# tally 3557.24, set at 3534 KB, 3529 GL., Cemented with 160 sacks of common, 10% salt, 5 sacks of salt flush job complete 7:00 a.m. 06-11-80. Float did hold

SAMPLE TOPS:

Anhydrite 1707"
B/Anhydrite 1735"

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Noon #6, SW NW NW, Section 18-5S-21W, Norton County, Kansas.

ABERCROMBIE DRILLING, INC.