

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-5-21W

Company- HONAKER-DAVIS DRLG. CO. ET AL
 Farm- Glennemeier No. 1

SEC. 15 T. 5 R. 21W
 NW NW SE

Total Depth. 3630'
 Comm. 3-5-59 Comp. 3-13-59
 Shot or Treated.
 Contractor. Honaker-Davis Drlg.
 Issued. 7-11-59

County Norton
 KANSAS



CASING:

8 5/8" 218' cem w/200 sx.

Elevation. 2176' RB

Production. Dry

Figures Indicate Bottom of Formations.

top soil & post rock	80
clay & sand	126
blue shale	218
shale & shells	1450
sand	1550
red bed & shale	1775
Anhydrite	1812
shale & shells	1975
shale w/lime strks	2040
shale & lime	2225
lime & shale	3108
lime	3230
lime & shale	3378
lime	3435
lime w/chert strks	3493
lime	3630 RTD
Total Depth	

TOPS:

Heebner	3332
Toronto	3357
Lansing-Kansas City	3372
Base Kansas City	3558
Reagan	3620

DST #1 3340-3435', op 60 mins, closed 20 min.
 good blow, rec. 585' muddy water, BHP 1120#,
 FP 60-385#.

DST #2 3527-3558', op 20 mins, closed 20 mins.
 weak blow 10 mins., rec. 15' mud. BHP 740#.

DST #3 3624-3630', op 60 mins., closed 20 mins.
 strong blow, rec. 2210' water, BHP 1000#,
 FP 400-1000#.