

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


25-5-21W

Company-Cities Service Oil Co.,
Farm- Finnigan No. 3

SEC. 25 T. 5 R. 21W
SW NE SE
1650' N. & 990' fr. W.
of SE/4
County Norton

Total Depth. 3695'
Comm. 10-3-57 Comp. 10-13-57
Shot or Treated.
Contractor. Lohmann+Johnson Drlg. Co.,
Issued. 12-21-57

KANSAS



Elevation. 2264' RB.

Production. 88 BOPD. 38 water

CASING:

8 5/8" @ 240' W/200 sks. cem.
5 1/2" @ 3692' W/200 sks. cem.

Figures indicate Bottom of Formations.

sand & shale	240
shale	540
shale & sand	1455
shale	1846
anhydrite	1884
shale & shells	2050
lime & shale	2170
shale	2360
lime & shale	2510
lime	3683
cored lime (rec. 5')	3682
cored lime & shale (rec. 3')	3691
cored shale & sand (no rec.)	3694
cored sand (no rec.)	3696
3696 R.T.D.-3695 S.L.M.	
Total Depth	3695

TOPS:

Corr. Topeka	3239
Corr. Heebner	3419
Corr. Dodge	3442
Corr. Lansing	3461
Corr. Base Kansas City	3643
Corr. Reagan	3692
Penetration	3
Corr. Total Depth	3695

Fill up

1445' oil in 30 minutes.
2199' oil in 1 1/2 hrs.
2367' fluid in 4 hrs.
2600' fluid in 8 hrs.
2305' oil & 300 wtr. in 19 hrs.