

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


27-5-21W

Company- D. G. HANSEN
Farm- Watkins No. 2

SEC. 27 T. 5 R. 21W
NE SE SE

Total Depth. 3684'
Comm. 5-7-58 Comp. 5-16-58
Shot or Treated.
Contractor. C-G Drig.
Issued. 7-12-58

County Norton
KANSAS



Elevation. 2253' KB

CASING:

8 5/8" 186.86'
5 1/2" 3670'

Production. 25 BOPD

Meas. from top of KB.

Figures indicate Bottom of Formations.

sand-shale	820
shale-sand	1250
shale-shell	1425
red bed	1620
red bed-shale	1796
Anhydrite	1826
shale	1925
shale-shell	2270
shale-lime-shell	2525
lime-shale	2850
shale-lime	3105
lime-shale	3291
lime	3375
lime-shale	3475
lime	3517
lime-shale	3590
lime	3671
lime-shale	3674
sand	3677
lime	3680 RTD
lime	3684 CTTD
Total Depth	

TOPS:

Anhydrite (scout)	1836
Topeka	3228
Heebner	3395
Toronto	3423
Lansing	3439
Base Kansas City	3625
Arbuckle	3668

DST #1 3496-3516, rec. 4' drilling
mud. BHP 160#.

DST #2 3669-74, op 1 hr, rec. 7' mud.

DST #3 3670-77, op 1 hr, rec. 7' CO &
3' HOCM. BHP 800#.