

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

7-5-21 W

Company. D. G. HANSEN
Farm. Noone

No. 1

SEC. 7 T. 5 R. 21W
SW SW SW

Total Depth. 3546

Comp. 5-21-57

Comp. 5-28-57


Shore. Treated.

Contractor. C-G Drilling Co.

Issued. 6-29-57

County Norton

KANSAS



Elevation. 2081 RB

Production. Dry

Figures Indicate Bottom of Formations.

surface soil	234
shale	730
sand	820
sand & shale	1200
sand	1460
red bed	1676
anhydrite	1715
shale	2160
lime & shale	3509
sand	3546
Total Depth	

TOPS:

Topeka	3017
Heebner	3214
Toronto	3237
Lansing	3256
Base KC	3443
Reagan sand	3505
Granite Wash	3524
Granite	3541

All RB meas.

DST #1: 3270-95, open 1 hr. wk. bl.
25 min. rec. 35' mud & possible oil
specks, IFP 40#, FFP 65#, IBHP 1275#,
FBHP 1010#.

DST #2: 3409-38, open 30 min. wk. bl.
3 min. rec. 7' mud, BHP 60#

DST #3: 3505-09, open 2 hrs. rec.
90' foamy oil, 10' mud, 70' SW, IFP
& FFP 0#, IBHP 1025#, FBHP 940#

DST #4: 3506-13, open 2 hrs. strg.
bl. thruout, rec. 70' wtry OCM, 730'
SOC SW, IBHP 1055#, FBHP 970#