

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


27-5-21W

Company- PHILLIPS PETROLEUM CO.
Farm- Wilt trout No. 3

SEC. 27 T. 5 R. 21W
NE NW SW

Total Depth. 3662'
Comm. 5-7-59 Comp. 6-9-59
Shot or Treated.
Contractor. Garvey Drlg.
Issued. 8-1-59

County Norton
KANSAS



Elevation. 2230' DF

Production. 86 BOPD - NW

CASING:

8 5/8" 433' cem w/300 sx.
4 1/2" 3657' cem w/110 sx.

Figures indicate Bottom of Formations.

surface clay, sand & shale 335
shale and shells 1300
shale 1670
red bed 1710
shale 1832
Anhydrite 1874
shale and shells 2780
lime and shale 3320
lime 3398
lime and shale 3545
lime 3662
Total Depth

TOPS: SCHLUMBERGER

Heebner 3376
Toronto 3405
Lansing-Kansas City 3422
Base Lansing-Kansas City 3607

SAMPLE TOP

Arbuckle 3656

Prod. Fmt. Arbuckle