

KANSAS

State Geological Survey
WICHITA BRANCH

28-5-21W 91

WELL COMPLETION REPORT AND
DRILLER'S LOG

S. 28 T. 5S R. 21 ^{X2X}W

API No. 15 — 137 — 20,204
County Number

Loc. 50' No. C NE/4


Operator
Hummon Corporation

County Norton

Address
400 One Main Place, Wichita, Kansas 67202

640 Acres
N

Well No. #2 Lease Name Williams



Footage Location
1270 feet from (N)XDD line 1320 feet from (E) (W) line

Elev.: Gr. 2319

Principal Contractor Red Tiger Drilling Company Geologist Tim Pierce

Spud Date 11/18/80 Date Completed Total Depth 3757 P.B.T.D.

DF 2321 KB 2324

Directional Deviation Oil and/or Gas Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8-5/8"	24#	267	Common	175	2% gel 3%cc
Production		4 1/2"	9.5#	3753	60-40 Poz	150	3/4 of 1% CFR2, .6 of 1% Halad 9, 10% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at
2 3/8"	3750	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/ 250 gal 7 1/2% mud acid.	
Treated w/ 1000 gal diesel fluid, 10 gal. hyflow.	

INITIAL PRODUCTION

Date of first production 1/12/81	Producing method (flowing, pumping, gas lift, etc.) pumping
RATE OF PRODUCTION PER 24 HOURS	Oil 20 bbls. Gas MCF 40 bbls. Water CFPB Gas-oil ratio
Disposition of gas (vented, used on lease or sold)	Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be trans-
mitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation
Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note
Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
Hummon Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Oil

Well No.
#2

Lease Name
Williams

S 28 T 5S R 21^{EX} W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<p>DST #1: 3478-3534 OP 30-45-30-30 Weak blow 1st open No blow 2nd open Flushed tool - weak blow died in 4 min.</p>	SIP	1071-908	<p><u>ELECT. LOG TOPS</u> Heebner Toronto Lansing B/KC Reagan LTD 3755</p>	<p>3469 -1145 3497 -1173 3515 -1191 3700 -1376 3751 -1427</p>
	FP	33-46		
<p>DST #2: 3532-3622 OP 45-60-45-90 Weak inc. to good blow Rec. 380' thin muddy water w/ few oil specks 120' muddy water</p>	SIP	1202-1202		
	FP	99-286		
<p>DST #3: 3748-3757' OP 45-60-60-90 Rec. 200' free oil (20°) 30' HMCO 30' thin OCM</p>	SIP	952-952		
	FP	66-88		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Wilber Berg
Signature

Wilber Berg

Title

1-29-81

Date