

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
500 East Murdock, Wichita, Kansas


34-5-21W

Company- SATURN DRILG, INC.  
Farm- Sullivan No. 1

SEC. 34 T. 5 R. 21W  
SE SE SW

Total Depth. 3697  
Comm. 5-13-52 Comp. 5-23-52  
Shot or Treated.  
Contractor.  
Issued. 6-21-52

County Norton  
KANSAS



CASING:  
8 5/8" 220' cem. w/125 sx

Elevation. 2261 DF

Production. Dry

Figures Indicate Bottom of Formations.

surface soil	40
sand	85
sand & lime	195
shale & shells	395
shale & sand	450
shale & shells	945
shale & shells & sand	1325
shale & red bed	1380
sandy lime	1415
sand	1580
shale	1615
shale & shells	1846
anhydrite	1885
shale	1895
shale & shells	2360
shale & lime	2525
lime & shale brks	2550
lime & shale	2765
lime	2825
lime & shale	3060
lime	3089
lime & shale	3295
shale	3320
lime	3375
lime & shale	3432
lime	3640
shale	3676
lime & shale	3686
lime, shale & pre-cambrian	3697
Total Depth	

Scout Tops:	
Heebner	3404
Toronto	3432
Lansing	3446
Eros, Arbuckle	3675
Reagan	3680
Schist	3682
Granite Wash	3684

DST: 3467-94' tool open  
1 hr. weak blow, rec.  
610' salt wtr

DST: 3501-24' tool open 1 hr.  
fair blow rec. 50' watery  
mud, 605' oily, muddy salt wtr.

DST: 3664-3697' tool open 30  
mins. weak blow for 3 mins.  
none for balance of test, rec.  
10' mud.

DST: 3488-3502' tool open 45  
mins. strong blow rec. 851'  
salt wtr.