

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


35-5-21W

Company- Cities Service Oil Company
Farm- Fox No. 1

SEC. 35 T. 5 R. 21W
NE SE NE
1650' S & 330' W. fr. NE

Total Depth. 3687'
Comm. 10-27-57 Comp. 11-5-57
Shot or Treated.
Contractor. Lohmann-Johnson Drl.,
Issued. 12-21-57

County Norton
KANSAS



CASING:
8 5/8" @ 240' w/200 sks. cem.

Elevation. 2249'

Production. Dry

Figures Indicate Bottom of Formations.

sand	40
shale	240
shale & sand	1000
shale	1809
anhydrite	1850
shale	2072
shale & lime	2240
lime & shale	2450
shale	2700
lime & shale	2860
shale & lime	2950
lime	3673
Cored lime & sand (rec. 3' 10")	3677
Cored lime & sand (Rec. 2' 10")	3680
Cored granite wash (Rec. 2')	3682
granite wash	3687
Total Depth	

TOPS:	
Topeka	3216
Heebner	3399
Dodge	3425
Lansing	3441
Base Kansas City	3631
Gorham	3676
Granite Wasg	3680
Pennsylvania	7'

Drill Stem Test:

#1 3675-87, open 1 hr., rec. 3'
oil and 37' heavily oil-cut mud; . 1.
B.H.P. 370# in 30 mins.,

Slope Tests (Syfo):

500' -0
1000' -1
1500' -1
2000' -1
2500' -1
3000' -2

7-7/8" Rotary Hole.