

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

36.5-21W

Company - CITIES SERVICE OIL CO.
Farm - Kitzke No. 3

SEC. 36 T. 5 R. 21W
NE NW SE

330' S and 990' E of Center

County. Norton
KANSAS

Total Depth. 3644'

Comm. 6-14-47

Comp. 8-27-47

Shot or Treated. 1000 gallons 7-9-47

Contractor. R. W. "In" Drilling Co.

Issued. 10-18-47

CASING:

8-5/8" 195' W/200 Sx. Cem.

5-1/2" 3634' W/150 Sx. Cem.

Elevation. 2211 ft & rh

Production. Phy. Pot: 35 oil,
22 wtr., 24 hrs. (8-23-47)

Figures Indicate Bottom of Formations.

surface clay	40
clay and shells	195
shale & shells	425
sand	470
shale & shells	2825
lime & shale	2935
shale & shells	3080
lime & shale	3230
lime	3460
lime & shale	3585
shale & sand	3637
3637 Rotary T.D. = 3635 S.L.M.	
sand	3643
granite wash	3644
Total Depth	3644
Schlumberger	

TOPS:

Lensing	3395'
Corr. Reagan	3632'
Granite Wash	3643'
Total Depth	3644'

1/2 bailer oil per hour.

perforate 11 shots 3628-39

Perforate 36 shots 3628-36

Hol. filled 1000' fluid
(k/3 water) 12 hours.

7-7/8" Rotary Hole.