

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

36-5-21W

Company- CITIES SERVICE OIL CO.
Farm- Kitzke No. 6

SEC. 36 T. 5 R. 21W
SW NE NW
1650' N 990' W of Cen.

Total Depth. 3664'

Comm. 6-23-57

Comp. 7-2-57


Shut or Tested.

Contractor Lohmann-Johnson Drlg., Co., Inc.

Issued 9-28-57

County Norton

KANSAS



Elevation. 2223

Production. Phy Pot. 156 oil, 3%
wtr. PD

8 5/8" 240' w/200 sx cem.
5 1/2" 3648' w/200 sx cem.
DV tool @ 1837' w/400 sx cem.

Figures indicate Bottom of Formations.

sand-shale	1590
shale	1795
anhydrite	1825
shale-shells	2050
shale	2460
shale-lime	2620
lime	2715
lime-shale	2845
lime	3595
lime-shale	3640
lime	3643
cored lime (rec. 4' 10")	3648
cored lime & sand (rec 2' 9")	3651
cored sand (no rec.)	3654
3654 RTD = 3651 SIM	
No record	3664
Total Depth	

TOPS:

Corr. Topeka	3191
" Heebner	3371
" Dodge	3396
" Lansing	3413
" Gorham sand	3647
" Reagan	3648
Pen	3'

Fill-up

409' oil in 45 min.
745' oil 1 hr. 45 mn.
2044' oil & 89' drilling wtr in
19 hrs. 45 min.