

12-5-22W

OPERATOR:
CONTRACTOR:
WELL NAME:
LOCATION:

SPUD DATE:
COMPLETION DATE:

R. P. Nixon
Abercrombie Drilling, Inc.
ARCHER-NELSON (SWD)
S/2 SW/4 SW/4 Section 12-5S-22W
Norton County, Kansas
March 13, 1976
March 14, 1976

0	45	Shale & Post rock
45	145	Blue Shale
145	780	Shale
780	860	Sand
860	1260	Shale
1260	1405	Sand
	1405	Rotary Total Depth

Spudded in @ 1:00 p.m. Drilled 230' of 12 $\frac{1}{4}$ " hole. Ran 6 jts. 8 5/8" casing, Tallied 219.38'. Set @ 227'. Cemented with 160 sx. Quick-Set cement. Plug was down @ 6:00 p.m. March 13, 1976.

Ran longstring, 43 jts. 5 $\frac{1}{2}$ " casing. Tallied 1402'. Set @ 1402'. Cemented with 300 sx. 50/50 Posmix, 6% gel. Plug was down @ 5:45 p.m. March 14, 1976.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)



Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the ARCHER-NELSON (SWD) S/2 SW/4 SW/4 Section 12-5S-22W, Norton County, Kansas.

ABERCROMBIE DRILLING, INC.

By:

Jerry A. Langrehr
Jerry A. Langrehr-Exec. V.P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state of of this 18th day of March, 1976.

Diane Steincamp
Diane Steincamp - Notary Public

My Commission Expires: February 18, 1980