

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


13-5-226

Company- BENNETT & ROBERTS DRIG., INC.
Farm- Bullock No. 2

SEC. 2713 T. 5 R22W
SE SE NE

Total Depth. 3616'
Comm. 8-22-58 Comp. 8-31-58
Shot or Treated.
Contractor. Bennett & Roberts Drlg.
Issued. 12-6-58

County Norton
KANSAS



CASING:

8 5/8" 212' w/125 sx. cem.

Elevation. 2179 RB

Production. Dry

Figures Indicate Bottom of Formations.

surface clay	20'
sand	60
shale	820
sand	900
shale & shells	1270
shale	1305
sand	1500
shale	1770
anhydrite	1790
shale and lime	3250
lime	3294
lime and shale	3355
lime	3360
lime and shale	3393
lime	3498
lime and shale	3598
lime, shale, granite & chert	3616
Total Depth	

FORMATION	SCHLUMBERGER ES	SCOUT
Anhydrite	-0-	1770 Driller
Topeka	3108	-0-
Heebner	3307	3307
Toronto	3333	3332
Lansing Kansas City	3353	3350
Base Kansas City	3538	3539
Granite Wash	3598	3598

DST #1 3336-3360 Presser Testers, Inc.
Tool open 1 hr., weak blow for 5 mins.
recovered 7' of drilling mud. IFP 40#
FFP 40#, BHP 345# in 20 minutes.

DST #2 2392-3421 Presser Tester Inc.
Tool open 1 hr. weak blow for 4 minutes
recovered 8' of rotary mud, shut in 20 mins.
IFP 0#, FFP 0#, BHP 550#.