

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


14-5-23W

Company- LEBEN DRILG, INC.
Farm- Delp No. 1

SEC. 14 T. 5 R. 23W
NW NW SE

Total Depth. 3760'
Comm. 7-25-56 Comp. 8-10-56
Shot or Treated.
Contractor.
Issued. 6-29-57

County Norton
KANSAS



CASING:
8" 160'

Elevation. 2156' DF

Production. Dry

Figures indicate Bottom of Formations.

NO DRILLERS LOG AVAILABLE.
All Meas. fr RKB. Schlumberger
Meas. of tops, zones & total
depth are taken as correct.

TOPS:	SAMPLE	SCHL.
Topeka	3142	3136
Heebner	3316	3314
Toronto	3340	3340
Lansing-Kansas City	3356	3356
B/Kansas City	3544	3546
Arbuckle	3708	3712

Tops: Scout
Marmaton 3566

cherty limestone: no
shows of oil or gas
observed 3341-46
limestone: no shows
of oil and/or gas
observed 3357-61
cherty limestone w/poor
to fair scattered oil:
slight shows free oil;
no odor. 3405-09 ✓
limestone; fair scat-
tered oil staining:
slight show free oil 3420-24 & ✓
3429-34 ✓
cyrsta lline to chalky
limestone; spotted oil
staining; tr free oil 3506-10 ✓
limestone; poor to good
spotted oil staining;
tr free oil 3519-22 ✓
limestone, tr oil
staining 3527-31 ✓
dolomite 3708-31
dolomite 3731-60

Total Depth

No shows of oil and/or gas
were observed in the Arbuckle
section.

DST #1 3405-3436 Open 30 min.
weak 1 min blow; Rec. 15' very
slightly OCM; BHP 850# in 15 min.

DST #2 3501-3531 Open 30 min.
weak 3 min. blow, rec. 3' mud
s/rainbow SO. BHP 55# in 15 min.