

22-5-23W


DERBY OIL-BAY PETRO-CROW DRIG.CO.
Delp No. 1.

SEC.22
CNE SE

T. 5 R. 23 W

Total Depth. 3897'
Comm. 6-11-42 Comp. 6-26-42
Shot or Treated.
Contractor. Crow Drig.Co.
Issued. 7-18-42

County. Norton



CASING:

8 5/8" 205' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

sand & surface clay	80
sand	110
shale & strks sand	157
shale	206
shale & shells	625
shale, shells, sft strks	
sand	1020
sand & shells	1119
lime & shale	1300
shale	1397
shale & sand strks	1480
sand & shale strks	1661
shale & shells	1780
shale	1900
anhydrite	1930
shale	2291
shale & sand	2416
shale	2571
sdv lime	2582
shale & shells	2600
shale	2662
lime sdv	2687
shale	2751
lime brkn	2768
shale & lime strks	2818
lime & shale	2855
shale	2865
shale & lime	2939
shale & lime strks	3069
shale & brkn lime	3126
lime	3239
shale	3248
lime	3619
shale & lime strks	3656
shale	3658
sand	3672
shale & lime	3734
shale	3790
conglomerate	3827
lime Arbuckle	3897
Total Depth.	

Ran Schlumberger Survey
No shows
Dry & Abnd.

Geological Data:
Anhydrite 1910
Ft. Riley 2470
Topeka 3247
Lansing 3447
Sdv Conglomerate 3787
Arbuckle 3822