

August, 1942.

Porter

Derby #1 Delp, (Belt)
C NE SE, 22-5S-23W,
Elevation 2280'±

Pennsylvanian conglomerate 3745-3822'

3745-3805 Not conglomerate proper. Scattered sand grains in
limes and clay shales.

3805-3822 Coarse sand, rare stained chert, red sandy grit, and
red shales.

Arbuckle Top 3822' Penetration 75' Sub-sea, minus 1542'

3822-3870 Dolomite, fine, white to pink. Belongs in interval
between Boyce sand and Everleigh. Probably Wiegel
at top and Pre-Wiegel below.

3870-3897 Everleigh sandy dolomite, medium, white to pink; with
pellets of glauconite.

ML