

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


6-5-26W

Company- R.W. SHIELDS
Farm- Feely "C" No. 1

SEC. 6 T. 5 R. 26W
NE SE NW

Total Depth. 3990'
Comm. 10-29-57 Comp. 11-6-57
Shot or Treated.
Contractor. Barnett Drlg. Co.
Issued. 1-11-58

County Decatur
KANSAS



Elevation. 2605' KB

Production. 25 BOPD

CASING:

8 5/8" 231' w/175 sx cem.
5 1/2" 3740' w/150 sx cem.

Figures indicate Bottom of Formations.

clay	120
sand	160
shale	230
shale	1205
shale-shells	1680
Anhydrite	1710
shale	1805
sand	1910
shale	2130
Anhydrite	2165
shale	2385
shale-li,e	2575
shale	2780
lime	3050
shale-lime	3440
lime	3825
shale	3980 RTD
shale	3990
Total Depth	

TOPS: KB	
Anhydrite	2130
Howard	3335
Topeka	3389
Heebner	3519
Toronto	3542
Lansing	3559
B/Kansas City	3751
sdv shale	3940
Weathered Granite	3953

DST #1 3570-90; Open 1 1/2 hrs.
Good blow throughout test.
SI 1/2 hr. Rec. 150' gas, 80'
clean oil, 60' muddy oil, BHP
1080#, FP 0-90.

DST #2 3607-40; Open 1 1/2 hrs.
Weak-fair blow throughout
test. SI 1/2 hr. Rec. 140' mud.
BHP 1130#. FP 0-30#.

DST #3 3677-3710 1/2 Open 45 min.
Weak blow for 7 min. SI 1/2 hr.
Rec. 3' mud. BHP 0#.

Perf. 3581-85; 3622-28; 3633-40.

Ran Welox Radiation Guard Log.