

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


1-5-27W

Company- R. W. SHIELDS  
Farm- Carter No. 1

SEC. 1 T. 5 R.27W  
NW NW SW

Total Depth. 3810  
Commi. 3-21-56 Comp. 3-29-56  
Shot or Treated.  
Contractor. Barnett Drilling, Inc.  
Issued. 5-5-56

County Decatur  
KANSAS



Elevation. 2640 DF

CASING:

8 5/8 @ 246' w/ 175 sx cmt.

Production. Dry

Figures indicate Bottom of Formations.

surface clay	40
shale & shells	95
sand	200
shale & shells	246
shale	1115
sand & shale	1535
shale	2184
anhydrite	2215
shale	2695
shale & lime	3550
lime	3690
shale & lime	3810
Total Depth	

TOPS: (DFM)

Anhydrite	2182
Cottonwood (?)	2931
Burlingame	3314
Howard	3363
Topeka	3431
Heebner	3560
Lansing	3600
Base K. C.	3791

DST #1: 3604-34, open 1½ hrs. fair  
bl. thruout, SI 30 min. rec. 185'  
SOCWM, FP 30-90#, BHP 1090#

DST #2: 3632-48, open 1½ hrs. wk. bl.  
thruout, SI 30 min. rec. 270' muddy  
wtr. FP 30-120#, BHP 1150#