


**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
 508 East Murdock, Wichita, Kansas

Company- CONTINENTAL OIL CO.  
 Farm- C. E. Feely No. 1

SEC. 2 T. 5 R. 27W  
 SE SE SW  
 330' fr SL & 2310' fr WL

Total Depth. 4042  
 Comm. 4-5-52 Comp. 5-6-52  
 Shot or Treated.  
 Contractor.  
 Issued. 6-21-52

County Decatur  
 KANSAS



Elevation. 2621 RB

**CASING:**

10 3/4" 256'  
 5 1/2" 3710'

Production. Phy. Pmp. Pot. 784  
 BO NW in 24 hrs.

Figures Indicate Bottom of Formations.

surface clay	40
shale & sand	820
shale, sand, & shells	1374
shale, shells & sand	1635
shale & sand	1935
shale & shells	2180
anhydrite	2216
shale	2256
shale & shells	2680
shale & lime	2940
lime	3004
lime & shale	3094
shale	3232
shale & lime	3373
lime	3580
lime & shale	3600
lime	3603
lime & shale	3917
shale	3985
lime & shale	4040
lime & shale	4042
Total Depth	

**Tops:**

Topeka	3371
Heebner	3550
Lansing	3591
Marmaton	3786
Arbuckle	3987