


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
502 East Murdock, Wichita, Kansas

Company- BURCH DRILLING CO., INC.
Farm- Feely No. 1

SEC. 27 T. 5 R. 27W
SW SE NE

Total Depth. 3845'
Comm. 5-19-59 Comp. 5-25-59
Shot or Treated.
Contractor.
Issued. 10-31-59

County Decatur
KANSAS



CASING:

8 5/8" 215' cem w/170 sx.
4 1/2" 3844'

Elevation. 2624' KB

Production. 80 BOPD

Figures Indicate Bottom of Formations.

shale	230
shale & shells	1839
shale	2210
Anhydrite	2255
shale & lime strks	2420
lime & shale	3650
lime	3845 RTD
Total Depth	

TOPS:

Heebner	3593
Toronto	3617
Lansing	3632
Base Kansas City	3833

DST #1 3603-3650', op 1 hr., rec. 315'
heavy oil gas cut mud plus 30' muddy
salt water. IBHP 550#/30 mins.,
IFP 0#, FFP 145#, FBHP 470#/30 mins.

DST #2 3665-3690', op 1hr., rec. 740'
salt water. IBHP 615#/30 mins., IFP 0#,
FFP 400#, FBHP 590#/30 mins.

DST #3 3702-3770', op 1 hr., rec. 120'
mud. IBHP 820#/30 mins., IFP 0#,
FFP 0#, FBHP 735#/30 mins.