

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

27-5-27W

COMPANY BURCH EXPLORATION

SEC. 27 T. 5 R. 27W

LOC. W $\frac{1}{2}$ W $\frac{1}{2}$ NE

FARM Feely

NO. 3

COUNTY Decatur

TOTAL DEPTH 3864'


COMM. 7-19-67

COMP. 7-30-67

SHOT OR TREATED

CONTRACTOR Abercrombie Drilling

ISSUED 10-7-67



CASING

20	10	
15	75/8"	220.5' cem w/ 125 sx
12	6	
13	5	
	4 1/2"	3863' cem w/ 150 sx

ELEVATION 2634' KB

PRODUCTION 52 BOPD, NW

Grav 36/ Lans 3802-06

NUMBERS INDICATE BOTTOM OF FORMATIONS

Oil & Gas Records Division
 State Geological Survey of Kansas

0	60
60	160
160	564
564	849
849	1200
1200	1600
1600	1897
1897	2039
2039	2080
2080	2252
2252	2285
2285	2440
2440	2651
2651	3023
3023	3125
3125	3864
	3864

Sand
Clay
Shale
Shale & Shells
Sand
Shale
Shale & Shells
Sand
Red Bed
Shale
Anhydrite
Shale
Shale & Shells
Lime & Shale
Lime & Shale
Lime
Rotary Total Depth

LOG TOPS
 Anhydrite (s) 2252
 B/ Anhydrite (s) 2285
 Heebner 3610
 Toronto 3632
 L Kansas City 3646
 B Kansas City 3851



Set 7-5/8", 26# casing at 220.5 with 125 sx. of cement.
 Ran 4-1/2" production casing and set at 3863' with 150 sx. of cement.

ELECTRIC LOG TOPS:

ELEVATION:

Anhydrite	2247	(+ 387)
Heebner	3610	(- 975)
Toronto	3632	(- 997)
Lansing	3647	(-1012)
B/K.C.	3847	(-1213)

2634	Kelly Bushing
2633	Derrick Floor
2627	Ground Level

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, A. L. Abercrombie, do hereby certify that the above and foregoing is a true and correct copy of the log of the Feely #3, W/2 W/2 NE/4 of Section 27-5S-27W, Decatur County, Kansas, as reflected by the files of Abercrombie Drilling, Inc.

A. L. Abercrombie