


KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

27-5-27W





COMPANY BURCH EXPLORATION

SEC. 27 T. 5 R. 27W
 LOC. NE NW SE

FARM Gillespie NO. 1

COUNTY Decatur

TOTAL DEPTH 3860'
 COMM. 12-16-67 COMP. 12-30-67
 SHOT OR TREATED
 CONTRACTOR Abercrombie Drlg.
 ISSUED 1-27-68



CASING

20	10	
15	8	5/8" 217' cem w/ 115 sx
12	6	
13	5	

ELEVATION 2631' KB

PRODUCTION DRY/BKG

0	160	Surface Clay & Sand
160	1090	Shale
1090	1550	Shale w/Pyrite Streaks
1550	2050	Shale
2050	2232	Shale (Red Bed)
2232	2265	Anhydrite
2265	2700	Shale
2700	2726	Shale & Lime
2726	2950	Lime & Shale
2950	3190	Shale & Lime
3190	3285	Lime & Shale
3285	3503	Shale & Lime
3503	3575	Lime & Shale
3575	3860	Lime
	3860	Rotary Total Depth



ELECTRIC LOG TOPS

ELEVATION

Anhydrite	2232	(+ 399)	2631 K. B.
Heebner	3604	(- 973)	2630 D. F.
Toronto	3628	(- 997)	2624 G. L.
Lansing	3642	(-1011)	
B/ K. C.	3848	(-1217)	
E.L.T.D.	3860	(-1229)	

Set 7" surface casing @217' w/115 sx. cement. Plug was down 12-16-67.
 Dry and Abandoned.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

A. L. Abercrombie, Abercrombie Drilling, Inc., do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 GILLESPIE, NE NW SE, Section 27-5S-27W, Decatur County, Kansas, as reflected by the files of Abercrombie Drilling, Inc.

A. L. Abercrombie
 A. L. Abercrombie