


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

27-5-27W

Company- CITIES SERVICE OIL CO.
Farm- Tice No. 1

SEC. 27 T. 5 R. 27W
SE SE SW
~~330' N & 330' W of S/4c~~
330 FSL: 3300 FGL - KCC
County Decatur
KANSAS

Total Depth. 3975
Comm. 12-15-52 Comp. 12-30-52
Shot or Treated. None
Contractor. Lohmann-Johnson Drilling Co., Inc.
Issued. 1-24-53



8 5/8 CASING:
202' w/ 250 sx cement

Elevation. 2690
2691 (2)
Production. Dry

Figures Indicate Bottom of Formations.

surface clay & sand	202
shale	1580
shale & sand	1925
shale, red bed & sand	2295
anhydrite	2342
shale & pyrite	2570
shale & shells	3105
lime & shale	3476
lime	3655
lime & shale	3737
lime	3906
lime & shale	3975
Total Depth	
TOPS:	
Topeka	3507
Heebner	3689
Dodge	3712
Lansing	3726
Base KC	3928

DST #1: 3717-37, open 1 hr. rec. 14'
mud w/ few specks oil-BHP 330# in 15 min.

DST #2: 3742-74, open 1 hr. rec. 15'
mud w/ few specks oil-BHP 400# in 15 min.